

ಕೊಡಗು ಜಿಲ್ಲಾ ಸಹಕಾರ ಕೇಂದ್ರ ಬ್ಯಾಂಕು ನಿ

ಕೇಂದ್ರ ಕಛೇರಿ : ಮಡಿಕೇರಿ

ಉನ್ನತಿ ಭವನ

ಜನರಲ್ ತಿಮ್ಮಯ್ಯ ವೃತ್ತ ಮಡಿಕೇರಿ

ವೆಬ್‌ಸೈಟ್: www.kodagudccb.com

ಮುಖ್ಯ ಕಾರ್ಯನಿರ್ವಹಣಾಧಿಕಾರಿ: 08272-228744



ಇ-ಮೇಲ್: adm@kodagudccb.com

ಪ್ರಧಾನ ವ್ಯವಸ್ಥಾಪಕರು :08272-228827

ಸಂಖ್ಯೆ:ಕೆ.ಡಿ.ಸಿ.ಸಿ/ಆಡಳಿತ/3011/2025-26

ದಿನಾಂಕ:11.11.2025

ಅಲ್ಪಾವಧಿ ಟೆಂಡರ್ ಪ್ರಕಟಣೆ

ಬ್ಯಾಂಕಿನ ಕುಶಾಲನಗರ ಶಾಖೆಯ ನೂತನ ಕಟ್ಟಡದಲ್ಲಿ ಆಂತರಿಕ ವಿನ್ಯಾಸದ (ಕೌಂಟರ್) ಕೆಲಸ ನಿರ್ವಹಿಸಲು ಅರ್ಹ ಗುತ್ತಿಗೆದಾರರಿಂದ ದರಪಟ್ಟಿಯನ್ನು ಅಹ್ವಾನಿಸಿದೆ.

ಕೆಲಸಗಳ ವಿವರ ಈ ಕೆಳಗಿನಂತಿದೆ:

ಕ್ರ. ಸಂ	ಶಾಖೆಯ ವಿಳಾಸ	ಕಾಮಗಾರಿಯ ವಿವರ	ಕೆಲಸ ಮಾಡಲು ನಿಗದಿಪಡಿಸಿದ ಗರಿಷ್ಠ ಅವಧಿ
1	ಕುಶಾಲನಗರ ಶಾಖೆ: 1ನೇ ಬ್ಲಾಕ್, ಬೈಚನಹಳ್ಳಿ ಕುಶಾಲನಗರ ಕುಶಾಲನಗರ ತಾಲೂಕು 571 234	ಆಂತರಿಕ ವಿನ್ಯಾಸ (ಕೌಂಟರ್) ಕೆಲಸದ ವಿಸ್ತೀರ್ಣಕ್ಕೆ ಅನುಗುಣವಾಗಿ ಚದರ ಅಡಿ ಲೆಕ್ಕದಲ್ಲಿ ನಮೂದಿಸುವುದು	15 ದಿನಗಳು
2	False Ceiling Work		

ಷರತ್ತುಗಳು:-

- ಕಾಮಗಾರಿಯ ದರಪಟ್ಟಿಯನ್ನು ನೀಡುವ ಪೂರ್ವದಲ್ಲಿ ಖುದ್ದಾಗಿ ಸ್ಥಳ ಪರಿಶೀಲಿಸಿ, ಕೆಲಸದ ಮಾಹಿತಿಯನ್ನು ಬ್ಯಾಂಕಿನ ಕೇಂದ್ರ ಕಛೇರಿಯನ್ನು ಸಂಪರ್ಕಿಸಿ ಪಡೆದುಕೊಳ್ಳಬಹುದಾಗಿದೆ.
- ಕಾಮಗಾರಿಗೆ ಬಳಸುವ ಸಾಮಗ್ರಿಗಳ ಮತ್ತು ಕೂಲಿ ವೆಚ್ಚಕ್ಕೆ (Cost of material and Labour Expenditure) ಸಂಬಂಧಿಸಿದಂತೆ ಪ್ರತ್ಯೇಕವಾಗಿ ದರಪಟ್ಟಿಯನ್ನು ಸಲ್ಲಿಸತಕ್ಕದ್ದು.
- ದರಪಟ್ಟಿಯ ಲಕೋಟೆಯ ಮೇಲೆ 'ಆಂತರಿಕ ವಿನ್ಯಾಸಕ್ಕೆ ಸಂಬಂಧಿಸಿದ ದರಪಟ್ಟಿ' ಎಂದು ನಮೂದಿಸಿ ಮುಚ್ಚಿದ ಲಕೋಟೆಯಲ್ಲಿ ದಿನಾಂಕ:24.11.2025ರ ಅಪರಾಹ್ನ 1.00 ಗಂಟೆಯ ಒಳಗೆ ಬ್ಯಾಂಕಿನ ಕೇಂದ್ರ ಕಛೇರಿಗೆ ಸಲ್ಲಿಸತಕ್ಕದ್ದು.
- ಹೆಚ್ಚಿನ ಮಾಹಿತಿಯನ್ನು ಬ್ಯಾಂಕಿನ ಅಧಿಕಾರಿಗಳ ಮೊಬೈಲ್ ಸಂಖ್ಯೆ:7619159005 ಅಥವಾ 8431148163ನ್ನು ಸಂಪರ್ಕಿಸಿ ಪಡೆಯಬಹುದಾಗಿದೆ.
- ದರಪಟ್ಟಿಯನ್ನು ಸ್ವೀಕರಿಸುವ ಅಥವಾ ರದ್ದುಪಡಿಸುವ ಹಕ್ಕನ್ನು ಬ್ಯಾಂಕಿನ ಆಡಳಿತ ಮಂಡಳಿಯು ಕಾಯ್ದಿರಿಸಿದೆ.

ಬ್ಯಾಂಕಿನ ಆಡಳಿತ ಮಂಡಳಿಯ ಒಪ್ಪಿಗೆ ಮೇರೆಗೆ

ಸಹಿ/-

ಮುಖ್ಯ ಕಾರ್ಯನಿರ್ವಹಣಾಧಿಕಾರಿ

**Quotation towards the Interiors for the proposed New Branch for KDCC Bank
Kushalnagar (only material), Kodagu**

Sl. No.	Particulars	Unit	Nos	L(feet)	B(feet)	H(feet)	Total	Unit Rate	Amount (Rs)
1	Manager's Cabin Using waterproof plywood of BWR grade with laminate of choice on both the sides of the partition. This also includes glass inlays in the partition too	Sft	1	20.00	10.00		200.00		
2	Managers Cabin table "L" shaped using plywood of BWR grade with laminate on the outside and the necessary drawers 2+2 nos with a top width for the table at 2.5ft in the front and 18" to the right with glass top	Sft	1	4	1.5	2.5	15		
			1	8	2	2.5	40		
							55		
3	Accounts section table using plywood of BWR grade with laminate on both the sides with the necessary drawers 3nos for a top width for the table at 3.0ft in the with granite table top	Sft	1	16	3	2.5	120		
			1	4	3	2.5	30		
			1	10	3	2.5	75		
							225		
4	Partition for the staff utility and the other partitions for pigmy AND JEWEL using plywood of BWR grade with laminate on both the sides	Sft	1	22	7.5		165		

5	Closed cash counter for the bank using plywood of BWR grade with laminate on both the sides with MS Roof grill	Sft	1	21	8		168		
6	Cash Counter table with two levels of table top with granite top to the width of the counter using BWR grade plywood using laminate on both the sides	Sft	1	6	2.5	2.5	37.5		
			1	6	1.5	1.5	13.5		
							51		
7	Fully closed shelf of 7ft wide made of plywood of BWR grade with laminate on both the sides	Sft	2	12	7	1.5	252		
8	Open shelf of 7ft wide made of plywood of BWR grade with laminate on both the sides	Sft	1	7	4	1.5	42		
	TOTAL								
	GST								
	GRAND TOTAL								

**Quotation towards the Interiors for the proposed New Branch for KDCC
Bank Kushalnagar(only Labour), Kodagu**

Sl no	Particulars	Amount(Rs)
1	Labour cost for the interior work of Kushalnagar branch	
	Total	
	Gst	
	Grand Total	

Providing false ceiling for the KDCCB bank building in Kushalnagar

Sl. No.	Particulars	Unit	Qty	Unit Rate	Amount(Rs)
1	Providing and fixing 7mm PVC Saint -gobain grid panels with centre black channel frame supports, including all hardware, fixtures and labour	Sft	1400		
2	Providing 2*2 LED lights in the false ceiling of 36 Watt equivalent of Havells/Philips/Bajaj made, with all required fixtures	No	18		
	Total				
	GST				
	Grand total				